

Supplemental/Bid Bulletin

Addendum No. 1
April 19, 2023

ITB No. DSWD7-PB-2023-16

Project Title: Completion/Repair/Improvement of AVRC II Storage Building, Street Lights and Other Facilities

Issued pursuant to Section 22.5 of the IRR of Republic Act 9184 to clarify and/or amend certain provision on the Bidding Documents issued for this project, considering the issues raised and clarifications made by prospective bidders during the Pre-bid Conference held on **April 19, 2023**, and shall form an integral part thereof, viz:

Subject	Amendment/Agreement/Clarification
Section VIII. Bill of Quantities	➤ Minor changes in Section VIII. Bill of Quantities were made.

Attached herewith is the revised **Section VIII. Bill of Quantities**.

This is for the guidance and information of all concerned.

Sgd. PATRICIA R. MEGALBIO
Chairperson, Bids and Awards Committee II

Section VIII. Bill of Quantities

Completion / Repair / Improvement of AVRC II Storage Building, Street Lights and Other Facilities					
ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL COST
PART I: GENERAL REQUIREMENTS					
1.1	Permits and Clearances	1.00	L.S.		
1.2	Project Billboard/Signboard -1set 4'X8' Construction Tarpaulin -1set 8'x8' COA Tarpaulin	1.00	each		
1.3	Occupational Safety and Health Program	1.00	lot		
1.4	Mobilization and Demobilization	1.00	L.S.		
1.5	Temporary Fence and storage rooms	1.00	L.S.		
SUB-TOTAL (PART I: GENERAL REQUIREMENTS)					
A. STORAGE BUILDING					
PART II: EARTHWORK					
2.1	Removal and Disposal of Structures, Obstruction and waste materials	1.00	L.S.		
2.2	Structure Excavation (Common Soil)	14.00	cu.m.		
2.3	Embankment & Compaction	91.00	cu.m.		
2.4	Gravel Fill	1.00	cu.m.		
2.5	Fill and Backfill (from borrow)	10.00	cu.m.		
SUB-TOTAL (PART II: EARTHWORK)					
PART III: PLAIN AND REINFORCED CONCRETE WORK					
3.1	Structural Concrete (Class A, 28 days), 3000 psi	50.00	cu.m.		
3.2	Reinforcing Steel (Deformed, Grade 40)	5,813.00	kg.		
3.3	Formworks, Falsework and Scaffoldings	240.00	sq.m.		
SUB-TOTAL (PART III: PLAIN AND REINFORCED CONCRETE WORK)					
PART IV: FINISHING					
4.1	Soil Poisoning	8.00	lit		
4.2	Catch Basin (CHB)	4.00	set		
4.3	Storm Drain and Downspout	1.00	L.S.		
4.4	Rainwater Tank, Stainless steel 304	1.00	L.S.		
4.5	Spandrel aluminum metal ceiling, 0.4mm thk. with ventilation holes	180.00	l.m.		

4.6	Fascia Board, 12mm Fiber Cement Board on metal frame	18.00	l.m.		
4.7	Louver Window	20.00	sq.m.		
4.8	Steel Roll Up Door	3.00	sets		
4.9	Fabricated Metal Roofing Accessories, gauge 24, flashings	32.40	L.m.		
4.10	Fabricated Metal Roofing Accessories, 0.6mm thk., valley rolls/gutter	18.00	L.m.		
4.11	Prepainted Galvanized Metal Sheets, 0.6mm thk. Rib Type, Long Span with 10mm thk, double sided insulation foam laid on G.I. screen	118.80	sq.m.		
4.12	Waterproofing of paraphet & canopy, (cement based)	284.00	sq.m.		
4.13	Painted Floor Finish (epoxy primer & epoxy enamel)	108.00	sq.m.		
4.14	Cement Plaster Finish	572.00	sq.m.		
4.15	Painting Works (Masonry/ Concrete)	572.00	sq.m.		
4.16	Painting Works (Steel)	56.00	sq.m.		
4.17	CHB (including Reinforcing Steel)150mm	286.00	sq.m.		
4.18	Structural Steel (Trusses)	1,024.00	kg.		
4.19	Structural Steel (Purlins)	882.00	kg.		
4.20	Metal Structures and Accessories - Bolts	32.00	pc.		
4.21	Metal Structures and Accessories - Steel Plates	68.00	kg.		
4.22	Metal Structures and Accessories - Sagrods	16.00	kg.		
4.23	Metal Structures and Accessories - Turnbuckle	6.00	pc.		
4.24	Metal Structures and Accessories - Cross Bracing	76.00	kg.		
4.25	Installation of Stainless-Steel Signage with backlights	1.00	lot		
SUB-TOTAL (PART IV: FINISHING)					
PART V: ELECTRICAL					
5.1	Conduits, Boxes and Fittings	1.00	L.S.		
5.2	Wires and Wiring Devices	1.00	L.S.		
5.3	Panelboard with Main and Branch Breakers	1.00	L.S.		
5.4	Lighting Fixtures and Lamps including emergency lights	1.00	L.S.		
SUB-TOTAL (PART V: ELECTRICAL)					

PART VI: MECHANICAL					
6.1	Ceiling Fan, 18" orbit type, 3-speed, 160 watts, heavy duty	12.00	set		
6.2	Fire Alarm and Sprinkler System (design, supply and installation)	1.00	L.S.		
SUB-TOTAL (PART VI: MECHANICAL)					
SUB-TOTAL (A. STORAGE BUILDING)					
B. SOLAR LIGHTS					
PART VII: EARTHWORK					
7.1	Removal of Structures and Obstructions	1	L.S.		
7.2	Structure Excavation	23	cu.m.		
7.3	Gravel Fill	3	cu.m.		
7.4	Fill and Backfill (from borrow)	16	cu.m.		
SUB-TOTAL (PART VII: EARTHWORK)					
PART VIII: PLAIN AND REINFORCED CONCRETE WORK					
8.1	Structural Concrete (Class A, 28 days)	12	cu.m.		
8.2	Reinforcing Steel (Deformed, Grade 40)	1034	kg.		
8.3	Formworks and Falseworks	51	sq.m.		
SUB-TOTAL (PART VIII: PLAIN AND REINFORCED CONCRETE WORK)					
PART IX: FINISHING					
9.1	Painting Works (Masonry/Concrete)	22	sq.m.		
9.2	Painting Works (Steel)	83	sq.m.		
9.3	Solar Lights with steel post, bolts, plates and other accessories	44	set		
SUB-TOTAL (PART IX: FINISHING)					
SUB-TOTAL (B. SOLAR LIGHTS)					
C. STORAGE VAN & 65m DRAINAGE					
PART X: GENERAL WORKS					
10.1	Removal and disposal of existing roofing, affected structures and obstruction	1	L.S.		
10.2	Structure Excavation (for drainage line)	17	cu.m.		
10.3	Concreting of Drainage Line, (Class A, 28 days), 3000 psi	10	cu.m.		
10.4	Reinforcing Steel (Deformed, Grade 40)	820	kg.		
10.5	Formworks and Falsework	52	sq.m.		
10.6	Steel Works (facia frame, steel gratings)	1486	kg.		

10.7	Catch Basin (CHB), 600mm x 600mm	8	set		
10.8	Spandrel aluminum metal ceiling, 0.4mm thk. with ventilation holes	270	l.m.		
10.9	Fascia Board, 12mm Fiber Cement Board on metal frame	35.8	l.m.		
10.10	Replacement of existing Doors, Solid panel Door with complete accessories in paint finish, 2sets- 2.1m x 0.8m	3.36	sq.m.		
10.11	Flashings, prepainted, oven-baked, fabricated galvanized iron, 0.6mm thk.	35.8	L.m.		
10.12	Valley Roll, prepainted, oven-baked, fabricated galvanized iron, 0.6mm thk.	14	L.m.		
10.13	Prepainted Galvanized Metal Sheets, 0.6mm thk. Rib Type, Long Span with 10mm thk, double sided insulation foam laid on G.I. screen	56	sq.m.		
10.14	Repainting of Storage Van, including grilles, railings, interior and exterior walls	331	sq.m.		
10.15	Installation of new Trusses	290	kg.		
10.16	Structural Steel (Purlins)	515	kg.		
10.17	Sagrods, 12mm dia. def. bar	18	kg.		
SUB-TOTAL (PART X: GENERAL WORKS)					
SUB-TOTAL (C. STORAGE VAN & 65m DRAINAGE)					
D. COVERED COURT					
PART XI: PAINTING WORKS					
11.1	Painting of Covered Court Flooring, including rectifying of floor cracks and potholes (epoxy primer & epoxy enamel)	672	sq.m.		
SUB-TOTAL (PART XI: PAINTING WORKS)					
SUB-TOTAL (D. COVERED COURT)					
TOTAL DIRECT COST FOR STORAGE BUILDING, SOLAR LIGHTS, STORAGE VAN & COVERED COURT					
TOTAL BID COST					